

# National Technical Systems Test Report for Environmental Testing of the VJ-4 Boroscope

#### **Prepared For**

ViewTech Borescopes | 1745 Barlow Street | Traverse City, MI 49686

### **Performed By**

National Technical Systems | 5325 Old Winter Garden Road | Orlando, FL 32811 | 407-293-5844 | www.nts.com

Matthew Matrisciano Technical Writer Andrew Kirkwood Environmental/Dynamic Manager

This report and the information contained herein represents the results of testing of only those articles/products identified in this document and selected by the client. The tests were performed to specifications and/or procedures approved by the client. National Technical Systems ("NTS") makes no representations expressed or implied that such testing fully demonstrates efficiency, performance, reliability, or any other characteristic of the articles being tested, or similar products. This report should not be relied upon as an endorsement or certification by NTS of the equipment tested, nor does it present any statement whatsoever as to the merchantability or fitness of the test article or similar products for a particular purpose. This document shall not be reproduced except in full without written approval from NTS.



# **Revision History**

Rev.	Description	Issue Date
0	Initial Release	09/20/2022



### **Table of Contents**

1.0	Intro	duction		4
2.0	Refer	ences		4
3.0			ion and Description	
	3.1	Securit	y Classification	4
4.0	Gene	ral Test R	Requirements	4
	4.1	Test E	quipment	4
5.0	Test I	Descriptio	ons and Results	5
	5.1		ive Atmosphere	
		5.1.1	Test Procedure	6
		5.1.2	Test Result	6
		5.1.3	Test Datasheets	
		5.1.4	Test Photographs	12
		5.1.5	Test Data	
		5.1.6	Test Equipment List	17
			List of Tables	
Table	3.0-1: Pr	oduct Ide	ntification - Equipment Under Test (EUT)	4
			f Test Information & Results	
rabie	5.1-1: EX	xpiosive A	tmosphere Test Equipment List	1/



#### 1.0 Introduction

This document presents the test procedures used and the results obtained during the performance of an Environmental test program. The test program was conducted to assess the ability of the specified Equipment Under Test (EUT) to successfully satisfy the requirements listed in Section 2.0.

#### 2.0 References

The following references listed below form a part of this document to the extent specified herein.

- Test Specification: MIL-STD-810G, Method 511.5, Procedure I
- ViewTech Borescopes Purchase Order(s) 1205, dated 09/20/2022
- National Technical Systems (NTS) Quote(s) OP0621789, dated 07/20/2022
- ISO/IEC 17025:2017(E) General Requirements for the Competence of Testing and Calibration Laboratories, dated 11/01/2017

### 3.0 Product Selection and Description

ViewTech Borescopes selected and provided the following test sample(s) to be used as the Equipment Under Test:

Table 3.0-1: Product Identification - Equipment Under Test (EUT)

Item	Qty.	Name/Description	Part Number	Serial Number
1	1	VJ-4 Boroscope	VJ4615FM-WL-XB	QXB2205311650

#### 3.1 Security Classification

Non-classified

### 4.0 General Test Requirements

### 4.1 Test Equipment

The instrumentation used in the performance of these tests is periodically calibrated and standardized within manufacturer's rated accuracies and are traceable to the National Institute of Standards and Technology. The calibration procedures and practices are in accordance with ISO 17025:2017. Certification of calibration is on file subject to inspection by authorized personnel.



# 5.0 Test Descriptions and Results

# **Table 5.0-1: Summary of Test Information & Results**

Section	Test	Specification	Test Facility	Test Date	Part #	Serial #	Test Result
5.1	Explosive Atmosphere	MIL-STD-810G, Method 511.5, Procedure I	Orlando	09/07/2022 - 09/07/2022	VJ4615FM-WL- XB	QXB220531165 0	Passed



# 5.1 Explosive Atmosphere

# **5.1.1** Test Procedure

The EUT was tested to MIL-STD-810G, Method 511.5, Procedure I.

# 5.1.2 Test Result

Test Result: The EUT passed.



### **5.1.3** Test Datasheets

	Certified Test Mate	rials
Description	Manufacturer	Lot Number
95% n-Hexane	Sigma-Aldrich	4503752071

		Data Recorder Se	tup	
Asset #	Channel	Type of Sensor	Function/Description	Unit
WC076352	1	Type-T Thermocouple	Chamber Air Temperature	°C
WC076352	2	Type-T Thermocouple	EUT Temperature	°C
WC076352	5	Type-T Thermocouple	Sample Chamber Air Temperature	°C
WC076352	11	Pressure Sensor	Main Chamber Pressure	PSIA
WC076352	12	Pressure Sensor	Sample Chamber Pressure	PSIA



Simulated Altitude (Feet)	Simulated Altitude (Meters)	Presssure (PSIA)
46,562	14,192	1.93
43,281	13,192	2.29
40,000	12,192	2.71
36,719	11,192	3.18
6,562	2,000	11.53
3,281	1,000	13.04
0	0	14.70

Pressure for altitudes was calculated in kPa using the MIL-STD-810G(CH1) Table 520.4-IV formula for altitudes ≤ 20,000 meters:

Pressure (kPa) = 101.33\*(((288-(6.5\*H))/288)^5.2558)

Pressure calculated in kPa was converted to psia per NIST Special Publication 1038 (May 2006), which lists 6.894757 kPa as equal to 1 psia, using the following formula:

Pressure (psia) = pressure (kPa) \* (1 psia / 6.894757 kPa)

#### Calculating Net Chamber Volume

measured chamber volume (ft3) – estimated test item volume (ft3) = net chamber volume (ft3)

32.62 0.08 32.54

**Quantity of Explosive Fuel Calculations** 

# [{net chamber volume [ft3] x chamber pressure [PSIA]}

(150.41) {\text{(net Chamber volume [15] x chamber pressure [150.42]}} {\text{(chamber temperature [° Rankine] x relative density of n-Hexane [0.659]})} = milliliters (ml) of fuel

added



Test	Witness
Name	Company
None	
Contain a Consti	d Comment Free Comment

	Customer-Suppli	ed Support Equipment	
Qty.	Description	Part/Model No.	Serial No.
	None		

#### Test Setup

The test hardware was placed in the chamber and subjected to the explosive atmosphere activities.



Step #   Activity	Test Co	nductor:	Dean Ressler	Lab Temperature:	27 °C	Lab Humidity:	55 %RH
1       Adjust the chamber temperature to 50 °C       9/7/2022       7:45       8:30       00:45         2       Stabilized the test hardware at 50 °C       9/7/2022       9:18       10:18       01:00         3       Adjusted to 14,192 meters ( 1.93 PSIA ) (2,000m above nominal)       9/7/2022       10:20       10:50       00:30         4       Injected 34.6 ml of n-Hexane into chamber (1,000m above nominal)       9/7/2022       10:50       10:51       00:01         5       Adjusted to 13,192 meters ( 2.29 PSIA ) (1,000m above nominal)       9/7/2022       10:51       11:01       00:10         6       Successfully ignited the sample chamber (1,000m above nominal)       9/7/2022       11:03       11:03       00:00         8       Adjusted to 11,192 meters ( 3.18 PSIA ) (2,000m above nominal)       9/7/2022       11:03       11:21       00:18         9       Stop test hardware operation (2,000m above nominal)       9/7/2022       11:03       11:21       00:18         9       Stop test hardware operation (2,000m above nominal)       9/7/2022       11:21       11:21       00:00         10       Successfully ignited the sample chamber (1.53 PSIA) (2,000m above nominal)       9/7/2022       11:21       11:21       00:00         11       Adjusted altitude to 2000 meters (11.53 PSIA)	C+ a = #		Activity	Data	Ctart Time	Final Time o	Duration
2       Stabilized the test hardware at 50 °C       9/7/2022       9:18       10:18       01:00         3       Adjusted to 14,192 meters (1.93 PSIA) (2,000m above nominal)       9/7/2022       10:20       10:50       00:30         4       Injected 34.6 ml of n-Hexane into chamber (2.29 PSIA) (1,000m above nominal)       9/7/2022       10:50       10:51       00:01         5       Adjusted to 13,192 meters (2.29 PSIA) (1,000m above nominal)       9/7/2022       11:01       11:02       00:01         6       Successfully ignited the sample chamber (1,000m above nominal)       9/7/2022       11:03       11:03       00:00         7       Begin test hardware operation (2,000m above nominal)       9/7/2022       11:03       11:03       00:00         8       Adjusted to 11,192 meters (3.18 PSIA) (2,000m above nominal)       9/7/2022       11:03       11:21       00:18         9       Stop test hardware operation (2,000m above nominal)       9/7/2022       11:23       11:21       00:18         9       Stop test hardware operation (2,000m above nominal)       9/7/2022       11:21       11:21       00:00         10       Successfully ignited the sample chamber (11.53 PSIA) (2,000m above nominal)       9/7/2022       11:22       11:23       00:01         11       Adjusted altitude to 20	<del>_</del> _	· · · · · · · · · · · · · · · · · · ·					
Adjusted to 14,192 meters ( 1.93 PSIA ) (2,000m above nominal)  A lnjected 34.6 ml of n-Hexane into chamber 9/7/2022 10:50 10:51 00:01  Adjusted to 13,192 meters ( 2.29 PSIA ) (1,000m above nominal)  Successfully ignited the sample chamber 9/7/2022 11:01 11:02 00:01  Begin test hardware operation 9/7/2022 11:03 11:03 00:00  Adjusted to 11,192 meters ( 3.18 PSIA ) (2,000m above nominal)  Stop test hardware operation 9/7/2022 11:03 11:21 00:18  Stop test hardware operation 9/7/2022 11:03 11:21 00:00  Successfully ignited the sample chamber 9/7/2022 11:03 11:21 00:00  Adjusted altitude to 2000 meters (11.53 PSIA) 9/7/2022 11:22 11:23 00:01  Adjusted altitude to 2000 meters (11.53 PSIA) 9/7/2022 11:23 11:42 00:19  Injected 153 ml of n-Hexane into chamber 9/7/2022 11:42 11:43 00:01  Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture 9/7/2022 11:53 11:54 00:01  Begin test hardware operation 9/7/2022 11:54 11:54 00:00  Adjusted altitude to site ambient (14.7 PSIA) 9/7/2022 11:54 11:54 00:00  Adjusted altitude to site ambient (14.7 PSIA) 9/7/2022 11:54 12:04 00:10  Stop test hardware operation 9/7/2022 12:04 12:04 00:00			<u>·</u>				
10:50   10:51   10:50   10:50   10:51   10:50   10:51   10:50   10:51   10:51   10:50   10:51   10:50   10:50   10:51   10:50   10:50   10:51   10:50   10:5	2			9/7/2022	9:18	10:18	01:00
5       Adjusted to 13,192 meters ( 2.29 PSIA ) (1,000m above nominal)       9/7/2022       10:51       11:01       00:10         6       Successfully ignited the sample chamber       9/7/2022       11:01       11:02       00:01         7       Begin test hardware operation       9/7/2022       11:03       11:03       00:00         8       Adjusted to 11,192 meters ( 3.18 PSIA ) (2,000m above nominal)       9/7/2022       11:03       11:21       00:18         9       Stop test hardware operation       9/7/2022       11:21       11:21       00:00         10       Successfully ignited the sample chamber       9/7/2022       11:22       11:23       00:01         11       Adjusted altitude to 2000 meters (11.53 PSIA)       9/7/2022       11:23       11:42       00:19         12       Injected 153 ml of n-Hexane into chamber       9/7/2022       11:42       11:43       00:01         13       Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture       9/7/2022       11:43       11:53       00:10         14       Successfully ignited the sample chamber       9/7/2022       11:54       11:54       00:01         15       Begin test hardware operation       9/7/2022       11:54       11:54       00:00	3			9/7/2022	10:20	10:50	00:30
1.000m above nominal   9/7/2022   10:51   11:01   00:10	4	Injected 34.6 ml of n-Hexane into chamber		9/7/2022	10:50	10:51	00:01
6         Successfully ignited the sample chamber         9/7/2022         11:01         11:02         00:01           7         Begin test hardware operation         9/7/2022         11:03         11:03         00:00           8         Adjusted to 11,192 meters ( 3.18 PSIA ) (2,000m above nominal)         9/7/2022         11:03         11:21         00:18           9         Stop test hardware operation         9/7/2022         11:21         11:21         00:00           10         Successfully ignited the sample chamber         9/7/2022         11:22         11:23         00:01           11         Adjusted altitude to 2000 meters (11.53 PSIA)         9/7/2022         11:23         11:42         00:19           12         Injected 153         ml of n-Hexane into chamber         9/7/2022         11:42         11:43         00:01           13         Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture         9/7/2022         11:43         11:53         00:10           14         Successfully ignited the sample chamber         9/7/2022         11:54         11:54         00:01           15         Begin test hardware operation         9/7/2022         11:54         12:04         00:10           16         Adjusted altitude to site ambient	5	-		9/7/2022	10:51	11:01	00:10
7         Begin test hardware operation         9/7/2022         11:03         11:03         00:00           8         Adjusted to 11,192 meters ( 3.18 PSIA ) (2,000m above nominal)         9/7/2022         11:03         11:21         00:18           9         Stop test hardware operation         9/7/2022         11:21         11:21         00:00           10         Successfully ignited the sample chamber         9/7/2022         11:22         11:23         00:01           11         Adjusted altitude to 2000 meters (11.53 PSIA)         9/7/2022         11:23         11:42         00:19           12         Injected 153         ml of n-Hexane into chamber         9/7/2022         11:42         11:43         00:01           13         Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture         9/7/2022         11:43         11:53         00:10           14         Successfully ignited the sample chamber         9/7/2022         11:53         11:54         00:01           15         Begin test hardware operation         9/7/2022         11:54         11:54         00:00           16         Adjusted altitude to site ambient (14.7 PSIA)         9/7/2022         12:04         12:04         00:10           17         Stop test hardware operatio	6	<u> </u>	· · · · · · · · · · · · · · · · · · ·	9/7/2022	11.01	11:02	00:01
8       Adjusted to 11,192 meters ( 3.18 PSIA ) (2,000m above nominal)       9/7/2022       11:03       11:21       00:18         9       Stop test hardware operation       9/7/2022       11:21       11:21       00:00         10       Successfully ignited the sample chamber       9/7/2022       11:22       11:23       00:01         11       Adjusted altitude to 2000 meters (11.53 PSIA)       9/7/2022       11:23       11:42       00:19         12       Injected 153       ml of n-Hexane into chamber       9/7/2022       11:42       11:43       00:01         13       Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture       9/7/2022       11:43       11:53       00:10         14       Successfully ignited the sample chamber       9/7/2022       11:53       11:54       00:01         15       Begin test hardware operation       9/7/2022       11:54       11:54       00:00         16       Adjusted altitude to site ambient (14.7 PSIA)       9/7/2022       11:54       12:04       00:10         17       Stop test hardware operation       9/7/2022       12:04       12:04       00:00							
9 Stop test hardware operation 9/7/2022 11:21 11:21 00:00 10 Successfully ignited the sample chamber 9/7/2022 11:22 11:23 00:01 11 Adjusted altitude to 2000 meters (11.53 PSIA) 9/7/2022 11:23 11:42 00:19 12 Injected 153 ml of n-Hexane into chamber 9/7/2022 11:42 11:43 00:01 13 Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture 9/7/2022 11:43 11:53 00:10 14 Successfully ignited the sample chamber 9/7/2022 11:53 11:54 00:01 15 Begin test hardware operation 9/7/2022 11:54 11:54 00:00 16 Adjusted altitude to site ambient (14.7 PSIA) 9/7/2022 11:54 12:04 00:10 17 Stop test hardware operation 9/7/2022 12:04 12:04 00:00		Adjusted to	11,192 meters ( 3.18 PSIA )				
10         Successfully ignited the sample chamber         9/7/2022         11:22         11:23         00:01           11         Adjusted altitude to 2000 meters (11.53 PSIA)         9/7/2022         11:23         11:42         00:19           12         Injected 153         ml of n-Hexane into chamber         9/7/2022         11:42         11:43         00:01           13         Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture         9/7/2022         11:43         11:53         00:10           14         Successfully ignited the sample chamber         9/7/2022         11:53         11:54         00:01           15         Begin test hardware operation         9/7/2022         11:54         11:54         00:00           16         Adjusted altitude to site ambient (14.7 PSIA)         9/7/2022         11:54         12:04         00:10           17         Stop test hardware operation         9/7/2022         12:04         12:04         00:00	9	, ,	·	9/7/2022	11.21	11.21	00:00
11       Adjusted altitude to 2000 meters (11.53 PSIA)       9/7/2022       11:23       11:42       00:19         12       Injected 153       ml of n-Hexane into chamber       9/7/2022       11:42       11:43       00:01         13       Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture       9/7/2022       11:43       11:53       00:10         14       Successfully ignited the sample chamber       9/7/2022       11:53       11:54       00:01         15       Begin test hardware operation       9/7/2022       11:54       11:54       00:00         16       Adjusted altitude to site ambient (14.7 PSIA)       9/7/2022       11:54       12:04       00:10         17       Stop test hardware operation       9/7/2022       12:04       12:04       00:00			<u>'</u>				
12     Injected 153     ml of n-Hexane into chamber     9/7/2022     11:42     11:43     00:01       13     Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture     9/7/2022     11:43     11:53     00:10       14     Successfully ignited the sample chamber     9/7/2022     11:53     11:54     00:01       15     Begin test hardware operation     9/7/2022     11:54     11:54     00:00       16     Adjusted altitude to site ambient (14.7 PSIA)     9/7/2022     11:54     12:04     00:10       17     Stop test hardware operation     9/7/2022     12:04     12:04     00:00	-						
13     Adjusted altitude to 1000 meters (13.04 PSIA) to obtain a homogeneous fuel/air mixture     9/7/2022     11:43     11:53     00:10       14     Successfully ignited the sample chamber     9/7/2022     11:53     11:54     00:01       15     Begin test hardware operation     9/7/2022     11:54     11:54     00:00       16     Adjusted altitude to site ambient (14.7 PSIA)     9/7/2022     11:54     12:04     00:10       17     Stop test hardware operation     9/7/2022     12:04     12:04     00:00				<u> </u>			
14         Successfully ignited the sample chamber         9/7/2022         11:53         11:54         00:01           15         Begin test hardware operation         9/7/2022         11:54         11:54         00:00           16         Adjusted altitude to site ambient (14.7 PSIA)         9/7/2022         11:54         12:04         00:10           17         Stop test hardware operation         9/7/2022         12:04         12:04         00:00		Adjusted altitude to 1000 meters (13.04 PSIA) to					
15     Begin test hardware operation     9/7/2022     11:54     11:54     00:00       16     Adjusted altitude to site ambient (14.7 PSIA)     9/7/2022     11:54     12:04     00:10       17     Stop test hardware operation     9/7/2022     12:04     12:04     00:00	1.4		· · · · · · · · · · · · · · · · · · ·	0/7/2022	11.52	11.51	00:01
16     Adjusted altitude to site ambient (14.7 PSIA)     9/7/2022     11:54     12:04     00:10       17     Stop test hardware operation     9/7/2022     12:04     12:04     00:00				<del>-                                    </del>			
17 Stop test hardware operation 9/7/2022 12:04 12:04 00:00	$\overline{}$						
		,	· ,				
			· · · · · · · · · · · · · · · · · · ·	<del>-                                    </del>			
	10	3466633	rany ignited the sample chamber	3/1/2022	12.04	12.03	00.01



Initials

DR

None

	Conclusion
A visual exam	ination of the test hardware after application of the environment did not reveal any notable changes
	or anomalies.
	The test hardware functioned properly and no anomalies were observed.
	operated at a simulated altitudes of 40,000 feet above site altitude and at site altitude using a e fuel-air mixture without igniting the explosive atmosphere in the main chamber.

Notes / Limitations / Deviations / Etc.



#### 5.1.4 **Test Photographs**





Receiving

**EUT Label** 



Setup for EUT Operation





Setup for EUT Operation



Setup for EUT Operation





EUT Thermocouple Placement





Explosive Atmosphere Setup



Explosive Atmosphere Setup



EUT in Test Chamber After Explosive Atmosphere Test



EUT in Test Chamber After Explosive Atmosphere Test








EUT in Test Chamber After Explosive Atmosphere Test


Shipping



# 5.1.5 Test Data









# **5.1.6** Test Equipment List

**Table 5.1-1: Explosive Atmosphere Test Equipment List** 

Asset Number	Asset Type	Manufacturer	Model	Calibrated	Due
WC056916	Chamber (Explosive Atmosphere)	Qualtest	DCEC1292	NCR	NCR
WC071987	Arm (Robot)	Mecademic	MECA500-R3	NCR	NCR
WC057023	Power Supply (DC)	Lambda	LH124FM-391	NCR	NCR
WC057057	Pump (Vacuum)	Bachmann Industries	50-WS	NCR	NCR
WC065432	Controller (Temperature)	Research	8630-111-00	NCR	NCR
WC067415	Controller (Temperature)	Love Controls	4B-33	NCR	NCR
WC067511	Cylinder (Graduated)	Fisherbrand Ertco	08-557D	NCR	NCR
WC067519	Computer (Laptop)	Hewlett Packard	Laptop	NCR	NCR
WC067552	Module (Input)	Fluke	2680A-180	NCR	NCR
WC071859	Controller (System)	JC Systems	600A-RTD/LIN	NCR	NCR
WC071940	Meter (Hygrometer)	Extech Instruments	445814	04/08/2022	04/08/2023
WC076352	System (Data Acquisition)	Fluke	2640A	11/18/2021	11/18/2022
WC076508	Power Supply (DC)	VOLTEQ	HY3020D	NCR	NCR

# **Calibration Abbreviations**

CAL: Calibration

NCR: No Calibration Required



**End of Test Report**